| A CONTRACT OF CONTRACT | North | Carolina State Environ Mi Certifie | | | | 4312 District Drive MSC 1918 Raleigh, NC 27699-1918 http://slph.ncpublichealth.com Phone: 919-733-7308 Fax: 919-715-8611 FINAL REPORT | | | | | | | | | |
|--|-----------------------------|---|----------|--|-----|---|------------------|---------------------|---------|-----------------------------------|--------------------------|-----------------------------------|----------------|------------|----------------------------------|
| Report to: Mike Painter WINSTON SALEM REGIONAL OFFICE PWSS 450 WEST HANES MILL RD STE 300 Winston Salem, NC 27105 | | | | Name of System: Wards MHP Lot 1 NC | | | | | | | | | | | |
| | | | | | | | | EIN: 566000372X | | Delivery: NC | Courier | | | | Guilford County |
| | | | | | | | | StarLiMS ID: ES1910 | 24-0033 | Date Collected: Date Received: | 10/23/2019 10/24/2019 | Time Collected: Time Received: | 13:10 07:44 | By: By: | Mike Painter Krystal Plemmons |
| Water System ID: 02 Facility ID: | -41-145 | System Type: | С | Water Source: Sample Type: | | Ground Water Special/Non-Compliance | | | | | | | | | |
| Sample Location: Kit Disinfectant Used: | chen Sink Tap | Location Type: Free Chlorine: | 1.1 mg/L | Location Code: Total Chlorine: | L01 | | | | | | | | | | |
| Comments: Dis | Disinfectant used: Chlorine | | | | | | | | | | | | | | |
| PWS - Colilert Profile | | | | | | Μ | lethod: SM 9223B | | | | | | | | |
| Analyte | Test Result | | Unit | Conclusion | | Date Tested | | | | | | | | | |
| Total Coliform E. coli | Absent Absent | | | | | 10/24/2019 10/24/2019 | | | | | | | | | |

Report Date:

10/28/2019

Reported By: **KPLEMMONS**

Explanations of Coliform Analysis:

If coliform bacteria are Absent, the water is considered safe for drinking purpose. If coliform bacteria are Present, the water is considered unsafe for drinking purpose. Presence of E. coli (bacteria) generally indicates that the water has been contaminated with fecal material. It must be remembered that a water analysis refers only to the sample received and should not be regarded as a complete report on the water supply.